



CITY OF FORTUNA
**ROHNER CREEK FLOOD CONTROL, SEISMIC AND
HABITAT IMPROVEMENT PROJECT**

Addendum No. 3

The purpose of this Addendum is to modify the Contract Documents for the subject project.

This Addendum, including attachments, shall become part of said Contract Documents.

Each bidder shall acknowledge receipt of this addendum in their bid proposal.

THE FOLLOWING ITEMS REFER TO THE NOTICE INVITING BIDDERS:

Item 1. REVISION: Section 1 has been modified below in red:

- 1. Bid Information.** The City of Fortuna (“Owner”), will accept separate sealed bids for **Phase A** and **Phase B** of the Rohner Creek Flood Control, Seismic and Habitat Improvements Project (“Project”), by or before ~~July 13,~~ **July 20,** 2016, at 3:00 p.m., at the office of GHD Inc., located at 718 3rd Street, Eureka CA, at which time the bids **for both Phases** will be publicly opened and read aloud. Owner reserves the right to reject any and all bids and to waive any non-substantive irregularities. **Bidders may submit a bid proposal for one or both Phases.** Each project phase requires a separate sealed bid submittal.

Item 2. REVISION: Section 2 has been modified below in red:

- 2.2 Time for Completion.** The planned timeframe for commencement and completion of construction of the Project is:

Phase A: Construction of Phase A is expected to occur in 2016. The owner anticipates awarding Phase A ~~in July~~ **on August 1,** 2016. Sixty one (61) calendar days are provided for time of completion. Commencement is planned for August 15th, 2016 and completion by October 14th, 2016.

THE FOLLOWING ITEM REFERS TO THE INSTRUCTION TO BIDDERS:

Item 3. REVISION: Section 3 has been modified below in red:

- 3. Requests for Information.** Questions regarding the Project, the bid procedures or any of the Contract Documents must be submitted by 3:00 p.m. ~~July 14,~~ **July 18,** 2016 in writing to:

THE FOLLOWING ITEMS REFER TO PART 3 - TECHNICAL SPECIFICATIONS:

Item 4. REVISION: Add the following underlined sentence to Part 2 Products, Section 1.03 SOURCE QUALITY CONTROL, item (B) of Section 03 37 13, Shotcrete:

- B.** Test samples in accordance with ACI 506.2. Test three cores, obtained from in-place shotcrete, for each work day or every 50 cubic yards placed, whichever is less. Location of cores to be approved by the construction manager.



Item 5. REVISION: Add the following underlined sentence to Part 2 Products, Section 2.01 MATERIALS, item (D) of Section 99 99 98, Tie Backs:

- D. Grout shall conform to the provisions in Section 50-1.09, "Bonding and Grouting," of the Standard Specifications. Fine aggregate may be added to the grout mixture of cement and water in drilled holes which are 8 inches or greater in diameter, but only to the extent that the cement content of the grout is not less than 845 pounds per cubic yard of grout. The minimum compressive strength for the grout shall be 1,500 psi at 3 days and 4,000 psi at 28 days. Fine aggregate, if used, shall conform to the provisions in Section 90-2, "Materials," and Section 90-3, "Aggregate Gradings," of the Standard Specifications.

Item 6. REVISION: Add the following underlined sentence to Part 2 Products, Section 2.01 MATERIALS, item (D) of Section 99 99 99, Soil Nails:

- D. Grout shall conform to the provisions in Section 46-3.02E, "Ground Anchors and Soil Nails - Grout," of the Standard Specifications. Fine aggregate may be added to the grout mixture of cement and water in drilled holes which are 6 inches or greater in diameter, but only to the extent that the cement content of the grout is not less than 845 pounds per cubic yard of grout. The minimum compressive strength for the grout shall be 1,500 psi at 3 days and 4,000 psi at 28 days. Fine aggregate, if used, shall conform to the provisions in Section 90-2, "Materials," and Section 90-3, "Aggregate Gradings," of the Standard Specifications.

THE FOLLOWING ITEMS REFER TO THE PLANS:

Item 7. REVISION: On sheet C107, call out "(N) FENCE TO MATCH EXISTING, TYPE D, 12 LF" shall be changed to read "(N) FENCE TO MATCH EXISTING, TYPE 3, 12 LF"

Item 8. REVISION: On sheet C109, call out "(N) FENCE TYPE B HEIGHT 6 FT, LENGTH 235 FT" shall be changed to read "(N) FENCE TYPE 2 HEIGHT 6 FT, LENGTH 235 FT"

Item 9. REVISION: On sheet C116, call out "(N) ACCESS GATE" shall be changed to read "(N) 12FT ACCESS GATE"

Item 10. REVISION: On the structural sheets, the soil nail and tie-back walls are called out with an initial shotcrete facing and final shotcrete facing. Various details call the final facing out as CIP concrete. The intent is that this final facing is shotcrete as well. However, if the contractor would like to use CIP concrete in place of shotcrete, this may be done given the CIP concrete meets the same requirements as the specified shotcrete.

THE FOLLOWING ITEM REFERS TO THE SWPPP:

Item 11. CLARIFICATION: In accordance to SWPPP requirements, the City will file a Notice of Intent (NOI) and Notice of Termination (NOT) for each Phase A and Phase B.

End of Addendum No. 3

July 11, 2016

Jeremy Svehla, P.E.

Date